HYDROLOGICAL CALCULATION RATIONAL METHOD (HP # 5 - 1989)

PROJECT : catchment 8 (During logging activity)
Tabung Haji, Pahang

A. CATCHMENT CHARACTERISTICS

From Topo Map sheets :
Area of catchment, Ac = 1.53 sq. km
Length of mainstream, L = 1.71 km
Percentage developed, = 75.00 % (Land use factor)

Weighted mean slope, s

li (km)	^h (m)	si =^h/li (%)	li*SQRT si
1.71	140.00	8.19	4.89
1.71	140.00	8.19	4.89

$$s = SQR\{ E(li * SQRT\ si) / E(li) \}$$
$$= \frac{4.89\ ^2}{1.71\ ^2}$$
$$= 8.19\ \%$$

B. LOCATION OF BRIDGE

From Topo Sheet No :

	o	'	"	
Longitude	102	18	0	E
Latitude	4	12	0	N

From figure 1 of HP # 5
Region No 4

Note : Region 1 - Perlis, Kedah, Perak
Region 2 - Kuala Lumpur
Region 3 - Johor
Region 4 - Kelantan, Terengganu, Pahang

C. ESTIMATION OF THE DESIGN RAINSTORM

1. Adopt return period, T = 2 years (HP # 1)

2. $Tc = \{1.286 \times L\} / \{A^{0.223} \times S^{0.263}\}$

$$= \frac{\{1.286 \times 1.71\}}{\{1.53^{0.223} \times 8.187134503^{0.263}\}}$$

= 1.15 hours

= 69.03 mins

3. Values of x (T,t)
(N.B. values of t is to envelope the value of Tc)

From Fig. 1 to 8 of HP # 1 :
x (2, 0.5) = 40 mm
x (20, 0.5) = 70 mm
x (2, 3) = 80 mm
x (20, 3) = 140 mm

4. Plot those values above on graph Figure 10 0f HP # 1

5. Read off values, with T = 2 years.

x (T , 0.5) = 75.00 mm
x (T , 3) = 120.00 mm

6. Plot values obtained in steps 3 and 5 on graph Fig. 9 of HP # 1.

7. Read off values :

With Tc = 1.15 hours
and T = 2 years.

x (2, 1.15) = 58.60 mm
x (20, 1.15) = 102.56 mm
x (T , 1.15) = 95.93 mm

8. Confidence limits

D = x (20) - x (2)
= 102.55781 - 58.604465
= 43.953349
0.43 D = 18.89994 mm

9. Max x (2) = x (T) + 0.43 D
[T = 2] = 95.930023 + 18.89994
= 114.83 mm

D. FLOOD ESTIMATION

1. From step C,

Max x (2) = 114.82996 mm
Therefore, i (2) = x (100) = 114.82996
Tc 1.150528
= 99.81 mm / hr

2. From Figure 4 with,

Region = 4
T = 2 years.

C10 = 0.38
Ct / C10 = 0.712

Therefore Ct = 0.27

3. Percentage developed = 75 %
Land use factor, F = 1.2

THEREFORE

Q max = F x 0.278 x Ct x i (T) x A
= 13.78 cu. m /s

E. DETERMINATION OF THE FLOOD WATER LEVEL AND VELOCITY

1. Plot cross-section of the river.
2. consider the recorded flood level as our first trial
3. Divide into sub-section
4. Stream slope at bridge site,

From the river survey plan :

Number of Part = 4 Section

Part	BedL1	BedL2	Length	Slope
1	6.880	6.544	60.000	0.006
2	6.544	6.067	25.000	0.019
3	6.067	6.037	25.000	0.001
4	6.037	5.604	20.000	0.022
5				
6				
7				

Average Slope, So 0.0118825

5. Calculation of Vm and Qc

Vi = Ri^(2/3) x So^(1/2) / ni

TRY Flood Level = 7.700 m OK

Sc.	Level (m)	Chng. (m)	Roughness ni	Area, A Sq.ft	Wetted perimeter (pi) (m)	Hydraulic Radius Ri=Ai/Pi (m)	Velocity vi (m/s)	Q=Vi Ai (cu.m)
0	9.200	0.000	0.045					
1	7.000	4.000	0.045	-1.600	4.565	-0.350	#NUM!	
2	6.741	18.000	0.045	11.613	14.002	0.829	2.138	24.832
3	5.857	23.100	0.045	7.145	5.176	1.380	3.003	21.458
4	5.792	27.000	0.045	7.314	3.901	1.875	3.684	26.944
5	5.272	33.600	0.045	14.309	6.620	2.161	4.049	57.941
6	6.344	38.000	0.045	8.325	4.529	1.838	3.635	30.261
7	6.659	42.500	0.045	5.393	4.511	1.196	2.729	14.717
8	7.000	50.500	0.045	6.964	8.007	0.870	2.207	15.370
9	9.200	54.000	0.045					
10								
			TOTAL	59.4634			TOTAL	191.52328

Type of bed material (Code) = 7 Rock

CODE	BED
1	Clay
2	Sandy Clay
3	Very fine sand
4	Fine sand
5	Fine Gravel
6	Rocky soil
7	Rock
8	Grass-lined

Therefore,

Mean velocity, Vm = E(Vi Ai) / E(Ai)

= 191.523277 / 59.4634

= 3.220859839 < 5.18 m/sec

Therefore OK

Discharge capacity, Qc = Vm x E(Ai)

= 191.523277 > 13.7829 cu.m

Therefore OK

HYDROLOGICAL CALCULATION RATIONAL METHOD (HP # 5 - 1989)

PROJECT : catchment 8 (During logging activity)
Tabung Haji, Pahang

A. CATCHMENT CHARACTERISTICS

From Topo Map sheets :
Area of catchment, Ac = 1.53 sq. km
Length of mainstream, L = 1.71 km
Percentage developed, = 75.00 % (Land use factor)

Weighted mean slope, s

li (km)	^h (m)	si =^h/li (%)	li * SQRT si
1.71	140.00	8.19	4.89
1.71	140.00	8.19	4.89

s = SQR{ E (li * SQRT si) / E (li) }

$$= \frac{4.89\ ^2}{1.71\ ^2}$$

= 8.19 %

B. LOCATION OF BRIDGE

From Topo Sheet No :

	o	'	"	
Longitude	102	18	0	E
Latitude	4	12	0	N

From figure 1 of HP # 5
Region No 4

Note : Region 1 - Perlis, Kedah, Perak
Region 2 - Kuala Lumpur
Region 3 - Johor
Region 4 - Kelantan, Terengganu, Pahang

C. ESTIMATION OF THE DESIGN RAINSTORM

1. Adopt return period, T = 5 years (HP # 1)

2. Tc = {1.286 x L} / {A^0.223 x S^0.263}

$$= \frac{\{1.286 \times 1.71\}}{\{1.53\ ^{0.223} \times 8.187134503\ ^{0.263}\}}$$

= 1.15 hours

= 69.03 mins

3. Values of x (T,t)
(N.B. values of t is to envelope the value of Tc)

From Fig. 1 to 8 of HP # 1 :
x (2, 0.5) = 40 mm
x (20, 0.5) = 70 mm
x (2, 3) = 80 mm
x (20, 3) = 140 mm

4. Plot those values above on graph Figure 10 0f HP # 1

5. Read off values, with T = 5 years.

x (T , 0.5) = 98.94 mm
x (T , 3) = 176.59 mm

6. Plot values obtained in steps 3 and 5 on graph Fig. 9 of HP # 1.

7. Read off values :

With Tc = 1.150528 hours
and T = 5 years.

x (2, 1.15) = 58.60 mm
x (20, 1.15) = 102.56 mm
x (T , 1.15) = 135.06 mm

8. Confidence limits

D = x (20) - x (2)
= 102.55781 - 58.604465
= 43.953349
0.43 D = 18.90 mm

9. Max x (5) = x (T) + 0.43 D
[T = 5] = 135.05778 + 18.89994
= 153.96 mm

D. FLOOD ESTIMATION

1. From step C,

Max x (5) = 153.95772 mm
Therefore, i (10) = x (100) = 153.95772
Tc 1.150528
= 133.81 mm / hr

2. From Figure 4 with,

Region = 4
T = 5 years.

C10 = 0.38
Ct / C10 = 0.88

Therefore Ct = 0.3344

3. Percentage developed = 75 %
Land use factor, F = 1.2

THEREFORE

Q max = F x 0.278 x Ct x i (T) x A
= 22.84 cu. m /s

HYDROLOGICAL CALCULATION RATIONAL METHOD (HP # 5 - 1989)

PROJECT : catchment 8 (During logging activity)
Tabung Haji, Pahang

A. CATCHMENT CHARACTERISTICS

From Topo Map sheets :
Area of catchment, Ac = 1.53 sq. km
Length of mainstream, L = 1.71 km
Percentage developed, = 75.00 % (Land use factor)

Weighted mean slope, s

li (km)	^h (m)	si =^h/li (%)	li*SQRT si
1.71	140.00	8.19	4.89
1.71	140.00	8.19	4.89

s = SQR{ E (li * SQRT si) / E (li) }

$$= \frac{4.89\ ^2}{1.71\ ^2}$$

= 8.19 %

B. LOCATION OF BRIDGE

From Topo Sheet No :

	o	'	"	
Longitude	102	18	0	E
Latitude	4	12	0	N

From figure 1 of HP # 5
Region No 4

Note : Region 1 - Perlis, Kedah, Perak
Region 2 - Kuala Lumpur
Region 3 - Johor
Region 4 - Kelantan, Terengganu, Pahang

C. ESTIMATION OF THE DESIGN RAINSTORM

1. Adopt return period, T = 10 years (HP # 1)

2. Tc = {1.286 x L} / {A^0.223 x S^0.263}

$$= \frac{\{1.286 \times 1.71\}}{\{1.53\ ^{0.223} \times 8.187134503\ ^{0.263}\}}$$

= 1.15 hours

= 69.03 mins

3. Values of x (T,t)
(N.B. values of t is to envelope the value of Tc)

From Fig. 1 to 8 of HP # 1 :
x (2, 0.5) = 40 mm
x (20, 0.5) = 70 mm
x (2, 3) = 80 mm
x (20, 3) = 140 mm

4. Plot those values above on graph Figure 10 0f HP # 1

5. Read off values, with T = 10 years.

x (T , 0.5) = 114.79 mm
x (T , 3) = 214.06 mm

6. Plot values obtained in steps 3 and 5 on graph Fig. 9 of HP # 1.

7. Read off values :

With Tc = 1.150528 hours
and T = 10 years.

x (2, 1.15) = 58.60 mm
x (20, 1.15) = 102.56 mm
x (T , 1.15) = 160.96 mm

8. Confidence limits

D = x (20) - x (2)
= 102.55781 - 58.604465
= 43.953349
0.43 D = 18.90 mm

9. Max x (10) = x (T) + 0.43 D
[T = 10] = 160.96376 + 18.89994
= 179.86 mm

D. FLOOD ESTIMATION

1. From step C,

Max x (10) = 179.8637 mm
Therefore, i (10) = x (100) = 179.8637
Tc 1.150528
= 156.33 mm / hr

2. From Figure 4 with,

Region = 4
T = 10 years.

C10 = 0.38
Ct / C10 = 1

Therefore Ct = 0.38

3. Percentage developed = 75 %
Land use factor, F = 1.2

THEREFORE

Q max = F x 0.278 x Ct x i (T) x A
= 30.32 cu. m /s

HYDROLOGICAL CALCULATION RATIONAL METHOD (HP # 5 - 1989)

PROJECT : catchment 8 (During logging activity)
Tabung Haji, Pahang

A. CATCHMENT CHARACTERISTICS

From Topo Map sheets :
Area of catchment, Ac = 1.53 sq. km
Length of mainstream, L = 1.71 km
Percentage developed, = 75.00 % (Land use factor)

Weighted mean slope, s

li (km)	^h (m)	si = ^h/li (%)	li * SQRT si
1.71	140.00	8.19	4.89
1.71	140.00	8.19	4.89

s = SQR{ E (li * SQRT si) / E (li) }
= 4.89 ^2 / 1.71 ^2
= 8.19 %

B. LOCATION OF BRIDGE

From Topo Sheet No :

	o	'	"	
Longitude	102	18	0	E
Latitude	4	12	0	N

From figure 1 of HP # 5
Region No 4

Note : Region 1 - Perlis, Kedah, Perak
Region 2 - Kuala Lumpur
Region 3 - Johor
Region 4 - Kelantan, Terengganu, Pahang

C. ESTIMATION OF THE DESIGN RAINSTORM

1. Adopt return period, T = 20 years (HP # 1)

2. Tc = {1.286 x L} / {A^0.223 x S^0.263}

= {1.286 x 1.71} / {1.53 ^0.223 x 8.187134503 ^0.263}

= 1.15 hours

= 69.03 mins

3. Values of x (T,t)
(N.B. values of t is to envelope the value of Tc)

From Fig. 1 to 8 of HP # 1 :
x (2, 0.5) = 40 mm
x (20, 0.5) = 70 mm
x (2, 3) = 80 mm
x (20, 3) = 140 mm

4. Plot those values above on graph Figure 10 0f HP # 1

5. Read off values, with T = 20 years.

x (T , 0.5) = 130.00 mm
x (T , 3) = 250.00 mm

6. Plot values obtained in steps 3 and 5 on graph Fig. 9 of HP # 1.

7. Read off values :

With Tc = 1.150528 hours
and T = 20 years.

x (2, 1.15) = 58.60 mm
x (20, 1.15) = 102.56 mm
x (T , 1.15) = 185.81 mm

8. Confidence limits

D = x (20) - x (2)
= 102.55781 - 58.604465
= 43.953349
0.43 D = 18.90 mm

9. Max x 20) = x (T) + 0.43 D
[T = 20] = 185.81339 + 18.89994
= 204.71 mm

D. FLOOD ESTIMATION

1. From step C,

Max x (20) = 204.71333 mm
Therefore, i (20) = x (100) = 204.71333
Tc 1.150528
= 177.93 mm / hr

2. From Figure 4 with,

Region = 4
T = 20 years.

C10 = 0.38
Ct / C10 = 1.128

Therefore Ct = 0.43

3. Percentage developed = 75 %
Land use factor, F = 1.2

THEREFORE

Q max = F x 0.278 x Ct x i (T) x A
= 38.93 cu. m /s

HYDROLOGICAL CALCULATION RATIONAL METHOD (HP # 5 - 1989)

PROJECT : catchment 8 (During logging activity)
Tabung Haji, Pahang

A. CATCHMENT CHARACTERISTICS

From Topo Map sheets :
Area of catchment, Ac = 1.53 sq. km
Length of mainstream, L = 1.71 km
Percentage developed, = 75 % (Land use factor)

Weighted mean slope, s

li (km)	^h (m)	si = ^h/li (%)	li * SQRT si
1.71	140.00	8.19	4.89
1.71	140.00	8.19	4.89

s = SQR{ E (li * SQRT si) / E (li) }

$$= \frac{4.89\ ^2}{1.71\ ^2}$$

= 8.19 %

B. LOCATION OF BRIDGE

From Topo Sheet No :

	o	'	"	
Longitude	102	18	0	E
Latitude	4	12	0	N

From figure 1 of HP # 5
Region No 4

Note : Region 1 - Perlis, Kedah, Perak
Region 2 - Kuala Lumpur
Region 3 - Johor
Region 4 - Kelantan, Terengganu, Pahang

C. ESTIMATION OF THE DESIGN RAINSTORM

1. Adopt return period, T = 50 years (HP # 1)

2. Tc = {1.286 x L} / {A^0.223 x S^0.263}

$$= \frac{\{1.286 \times 1.71\}}{\{1.53\ ^{0.223} \times 8.187134503\ ^{0.263}\}}$$

= 1.15 hours

= 69.03 mins

3. Values of x (T,t)
(N.B. values of t is to envelope the value of Tc)

From Fig. 1 to 8 of HP # 1 :
x (2, 0.5) = 40 mm
x (20, 0.5) = 70 mm
x (2, 3) = 80 mm
x (20, 3) = 140 mm

4. Plot those values above on graph Figure 10 0f HP # 1

5. Read off values, with T = 50 years.

x (T , 0.5) = 149.68 mm
x (T , 3) = 296.52 mm

6. Plot values obtained in steps 3 and 5 on graph Fig. 9 of HP # 1.

7. Read off values :

With Tc = 1.150528 hours
and T = 50 years.

x (2, 1.15) = 58.60 mm
x (20, 1.15) = 102.56 mm
x (T , 1.15) = 217.98 mm

8. Confidence limits

D = x (20) - x (2)
= 102.55781 - 58.604465
= 43.953349
0.43 D = 18.89994 mm

9. Max x (50) = x (T) + 0.43 D
[T = 50] = 217.9787 + 18.89994
= 236.88 mm

D. FLOOD ESTIMATION

1. From step C,

Max x (50) = 236.87864 mm
Therefore, i (50) = x (100) = 236.87864
Tc 1.150528
= 205.89 mm / hr

2. From Figure 4 with,

Region = 4
T = 50 years.

C10 = 0.38
Ct / C10 = 1.296

Therefore Ct = 0.49

3. Percentage developed = 75 %
Land use factor, F = 1.2

THEREFORE

Q max = F x 0.278 x Ct x i (T) x A
= **51.75 cu. m /s**

HYDROLOGICAL CALCULATION RATIONAL METHOD (HP # 5 - 1989)

PROJECT : catchment 8 (During logging activity)
Tabung Haji, Pahang

A. CATCHMENT CHARACTERISTICS

From Topo Map sheets :
Area of catchment, Ac = 1.53 sq. km
Length of mainstream, L = 1.71 km
Percentage developed, = 75 % (Land use factor)

Weighted mean slope, s

li (km)	^h (m)	si =^h/li (%)	li*SQRT si
1.71	140.00	8.19	4.89
1.71	140.00	8.19	4.89

$$s = SQR\{ E(li * SQRT\ si) / E(li) \}$$
$$= \frac{4.89\ ^2}{1.71\ ^2}$$
$$= 8.19\ \%$$

B. LOCATION OF SITE

From Topo Sheet No :

	o	'	"	
Longitude	102	18	0	E
Latitude	4	12	0	N

From figure 1 of HP # 5
Region No 4

Note : Region 1 - Perlis, Kedah, Perak
Region 2 - Kuala Lumpur
Region 3 - Johor
Region 4 - Kelantan, Terengganu, Pahang

C. ESTIMATION OF THE DESIGN RAINSTORM

1. Adopt return period, T = 100 years (HP # 1)

2. $Tc = \{1.286 \times L\} / \{A^{0.223} \times S^{0.263}\}$

$$= \frac{\{1.286 \times 1.71\}}{\{1.53^{0.223} \times 8.187134503^{0.263}\}}$$

$$= 1.15 \text{ hours}$$

$$= 69.03 \text{ mins}$$

3. Values of x (T,t)
(N.B. values of t is to envelope the value of Tc)

From Fig. 1 to 8 of HP # 1 :
x (2, 0.5) = 40 mm
x (20, 0.5) = 70 mm
x (2, 3) = 80 mm
x (20, 3) = 140 mm

4. Plot those values above on graph Figure 10 0f HP # 1

5. Read off values, with T = 100 years.

x (T , 0.5) = 164.43 mm
x (T , 3) = 331.38 mm

6. Plot values obtained in steps 3 and 5 on graph Fig. 9 of HP # 1.

7. Read off values :

With Tc = 1.15 hours
and T = 100 years.

x (2, 1.15) = 58.60 mm
x (20, 1.15) = 102.56 mm
x (T , 1.15) = 242.08 mm

8. Confidence limits

D = x (20) - x (2)
= 102.55781 - 58.604465
= 43.953349
0.43 D = 18.90 mm

9. Max x (100) = x (T) + 0.43 D
[T = 100] = 242.08207 + 18.89994
= 260.98 mm

D. FLOOD ESTIMATION

1. From step C,

Max x (100) = 260.98 mm
Therefore, i (100) = $\frac{x\ (100)}{T\ c}$ = $\frac{260.98201}{1.150528}$
= 226.84 mm / hr

2. From Figure 4 with,

Region = 4
T = 100 years.

C10 = 0.38
Ct / C10 = 1.46

Therefore Ct = 0.5548

3. Percentage developed = 75 %
Land use factor, F = 1.2

THEREFORE

Q max = F x 0.278 x Ct x i (T) x A
= **64.23 cu. m /s**